GENERATOR QUOTATION

TEMS-DEMO-SINGLE
12 Oct 2026 / R00

Prepared for

Sample Industries Pvt. Ltd.

Kolhapur, Maharashtra

125 kVA

DIESEL GENERATING SET

3 Phase / Quantity 1



Representative product artwork. Configuration varies by model.

YOUR PROPOSED SYSTEM

125 kVA

3 Phase / Quantity 1 / Mahindra Powerol

YOUR PROPOSAL

Equipment details / Your offer / Commercial terms

Review the equipment, followed by pricing and commercial terms.

REFERENCE

Meeting / 11 Oct 2026

DEMONSTRATION ONLY. Illustrative prices; not a commercial offer.

VALID UNTIL 20 OCT 2026

The price schedule is followed by the final commercial terms.

01 / EQUIPMENT FEATURES

DG features

Built around your power requirements.

Applies to: 125 kVA / 3 Phase

Product salient features

- Designed for economical operation and maintenance, with a proven engine for rugged use.
- Service interval: 500 operating hours / one year, subject to the selected model's confirmed maintenance schedule.
- Wide service network across India, with coordinated sales, service and spares support.
- CPCB IV+ emission compliance and remote monitoring are subject to confirmation for the selected model and scope.
- Compact footprint to support efficient use of installation space.
- Single-window warranty support; warranty duration and any extended 5C cover follow the confirmed commercial terms.

ENGINE



- Mahindra four-stroke, inline, liquid-cooled engine.
- Mechanical engine configuration and fuel-consumption performance to be confirmed for the selected model.
- Dry air cleaner with indicator.
- Electric starter motor and battery-charging alternator.
- Lubricating oil and coolant supplied prefilled.
- Starting battery: one 12 V DC battery where applicable; confirm the selected model's starting system.
- Nominal engine speed: 1500 rpm, subject to model confirmation. Engine model and rated output are listed in the technical specifications.

ALTERNATOR



- Brushless, revolving-field, self-excited design.
- H-class insulation.
- Compact, lightweight construction with sealed bearings.
- IS/IEC 60034-1 conformity, subject to confirmation for the supplied alternator.
- Voltage, phase rating, power factor and permitted load imbalance must match the confirmed supplied configuration.
- Selected kVA and kW ratings are listed in the technical specifications.

General feature descriptions; final equipment configuration, certification and included scope must be confirmed for the selected model. Model ratings are listed in the technical specifications.
Component images are representative of the equipment family.

01 / EQUIPMENT FEATURES

Controls & enclosure

Monitoring, protection and practical service access.

Applies to: 125 kVA / 3 Phase



Representative control panel

CONTROLLER

- SEDEMAC GC111X family controller, where specified, with ARM-based processing, graphic LCD and backlit display.
- Operating modes: AMF, manual and remote start/stop for supported single-phase and three-phase systems.
- Engine monitoring: oil pressure, coolant temperature, fuel level, battery condition and running hours.
- Alternator monitoring: line-to-neutral and line-to-line voltage, current, kW/kVA, frequency and power factor.
- Engine protections: low oil pressure, high temperature, overspeed, sensor faults, low fuel and battery-voltage faults.
- AC protections: under/over voltage and frequency, overload, load imbalance and sensing faults.
- Maintenance alerts based on running hours and service due date.
- Communication interfaces: USB, RS485 and CAN; configuration through the front panel.

Confirm the controller model and enabled functions for the supplied system. AMF operating capability does not mean that a separately priced AMF panel is included.



Representative DG enclosure

ACOUSTIC ENCLOSURE

- Designed to meet applicable MoEF / CPCB requirements; confirm certification for the supplied enclosure and DG set.
- Operating range of 10 to 55 degrees C without external cooling is subject to confirmation for the selected model and site conditions.
- Fade-resistant, UV-resistant powder-coated finish.
- Fire-retardant acoustic insulation using PU foam or rockwool, as specified for the supplied enclosure.
- Draw-out fuel tank for maintenance, with external fuel-filling provision outside the canopy.
- Compact footprint with easy access to serviceable components.
- Common mild-steel base frame with anti-vibration mounting pads.
- Emission after-treatment system (ATS), as applicable to the confirmed model.
- Model-specific dimensions and fuel-tank capacity are listed in the technical specifications.

General feature descriptions; final equipment configuration, certification and included scope must be confirmed for the selected model. Model ratings are listed in the technical specifications.

02 / EQUIPMENT DETAILS

Technical specifications

The equipment behind your quotation.

125 kVA

3 Phase / Option 1

DIESEL GENERATING SET

Model: H4485G1

Power: 100 kWe

Representative image. Final specification and supply scope are as quoted.



Specification	Details
Power rating	100 kWe
Engine model	H4485G1
Engine output	156 BHP
Dimensions (L x W x H)	3950 x 1350 x 1425 mm
Fuel tank	250 L

Legacy catalog specifications; confirm model, phase availability and current manufacturer specifications before order.

03 / YOUR OFFER

Price schedule

PREPARED FOR

Sample Industries Pvt. Ltd.

Kolhapur, Maharashtra

Attn: Purchase department

QUOTATION REFERENCE

TEMS-DEMO-SINGLE

Lead: DEMO-001

Meeting / 11 Oct 2026

DEMONSTRATION ONLY. Illustrative prices; not a commercial offer.

Description	Qty	Unit rate INR	GST INR / rate	Amount incl. GST, INR
Mahindra Powerol 125 kVA - 3 Phase	1	3,85,000.00	69,300.00 @ 18%	4,54,300.00
Transportation (per offer)	1	8,000.00	1,440.00 @ 18%	9,440.00
AMF panel	1	16,500.00	2,970.00 @ 18%	19,470.00
Installation and commissioning	1	25,000.00	4,500.00 @ 18%	29,500.00
Basic amount INR 4,34,500.00				GST INR 78,210.00

YOUR QUOTATION TOTAL
Including GST. Optional extras excluded.

INR 5,12,710.00

04 / THE DETAILS THAT MATTER

Commercial terms

A clear scope, from order to delivery.

Pricing & taxes	All amounts are in INR. The offer total includes GST at the itemized rates. Separately listed optional extras are excluded.
Offer validity	8 days from 12 Oct 2026; valid until 20 Oct 2026. Prices are subject to reconfirmation after this date.
Payment	100% advance for immediate delivery, or 30% advance with the order and the balance 70% against pro forma invoice before dispatch.
Delivery	2-4 weeks from receipt of order and advance, subject to availability and written confirmation.
Warranty	As per the applicable manufacturer warranty for the selected model, to be confirmed in the order acknowledgement.
Scope of supply	Supply is limited to the equipment and services explicitly priced as included in this quotation. Optional items are excluded from the offer total unless accepted separately.
Exclusions	Unpriced unloading, civil foundation, earthing, power and control cabling, exhaust piping, changeover switches and installation are excluded. Statutory approvals are to the customer account. Transit insurance is excluded unless expressly included in a priced line.
Additional terms	SAMPLE DOCUMENT. Replace all example prices and customer details before use. Customer to mention GST/TAN/PAN and date on the purchase order. If delivery is deferred, a revised schedule and any price implications will be mutually agreed. Cancellation charges: 2.5% of the basic order value. Disputes are subject to arbitration under the Arbitration and Conciliation Act, 1996, at the applicable jurisdiction.

READY TO TAKE THE NEXT STEP?

We look forward to supporting your power requirement.

For Techno Electromechs

Venkatesh Bhat

9823012044 / 9022330752

techno.tems@gmail.com

Registered address: 54/15 A, SHRI-NIVASA, Near Vasantrao Chougule School, Morewadi Road, Kolhapur - 416004
Sales office: Opp. Sudharshan Petrol Pump, near Bagavati Mangal Karyalay, NH-04, Gokulshirgaon, Kolhapur - 416234.